

## **Quote for Widening Caton rd. to Acceptable City/County Standards**

**A quote to fill the property was submitted by Blalock & Sons indicating that the approximate cost to bring Caton Rd. to acceptable City County Standards would as follows: \$65,000 - \$165,000**

It looks like around 1100' of length of Caton Road is all that will be needed be considered to get from the Parkway and enter the initial gravel driveway. Estimating that length at 26' wide, the total removal and rebuild option would be \$165,000. But, Caton Rd. has been recently overlaid by the City and is approximately 22' wide presently. So I think that they would require only 22' of existing just to be overlaid with the 2 layers of asphalt and potentially full depth for 2' on either side of the road to get to the required 26' width. That would cost \$115,000. However, I think even that is excessive from a depth consideration. They should only require a 2" overlay with the full depth 4' widening. That would only cost \$65,000. As you can see, it all depends on the end use, and then the City's reasonable expectations considering the condition and existing width of the existing City Street. Let me know if you need anything else Thanks!

***See email quote on quote on website.***